Chapter 6

Perception as Inference: How the Brain Sees What It Expects

> *"Such objects are always imagined as being present in the field of vision as would have to be there in order to produce the same impression on the nervous mechanism, the eyes being used under ordinary normal conditions."*
>
> *— Hermann von Helmholtz, Treatise on Physiological Optics (1867)*

The Problem Perception Solves

Chapter 1 said, almost in passing, that perception is an active process of inference shaped by prior experience. Every chapter since has built the machinery that makes the sentence true: neurons that integrate evidence, circuits that amplify and compare, neuromodulators that set the context, and synapses that turn experience into structure. This chapter uses that machinery to answer a question that sounds too simple to need one. When you open your eyes, why do you see a world rather than a pattern of light?

The light that reaches the retina is not a world. It is a two-dimensional projection, blurred by the optics of the eye, sampled by a mosaic of receptors, and interrupted three times a second by eye movements. Worse, the projection is ambiguous in a way that no amount of resolution can fix. A trapezoid on the retina can be a trapezoid face on, a rectangle receding from the viewer, or a painted shape on a billboard; the retina cannot distinguish them, because they all produce the same image (Figure 6.1). A patch of grey can be a dark surface in bright light or a bright surface in shadow. A sound that grows louder can be a source approaching or a source turning toward you. Mathematically this is an inverse problem, and inverse problems of this kind are ill-posed: the evidence does not determine the answer.




Figure 6.1. The inverse problem. Many arrangements of surfaces in the world produce the same image on the retina. The evidence alone cannot say which one is present.

Helmholtz saw this clearly in the 1860s and drew the only possible conclusion. If the evidence does not determine the answer and yet we perceive an answer, something must be supplying the rest. He called it unconscious inference: the perceptual system settles on the state of the world that, under ordinary conditions, would most probably have produced the sensations it is receiving.[1] The judgment is not made by reasoning and cannot be overruled by it, which is why an illusion persists after you know it is an illusion. A century and a half later the idea has been made precise, mapped onto cortical anatomy, and measured with electrodes, and this chapter is an account of that work. The thesis can be stated in one sentence. Perception is not the reading of a signal but the construction of a hypothesis, built from what the senses report and from what the brain already expects, and weighted by how much each can be trusted.

The Senses Deliver Evidence, Not Pictures

Begin with what the senses actually provide, because it is less than intuition suggests.

The human retina has roughly a hundred million rods and six million cones, but only about a million ganglion cell axons leave each eye.[2] The retina therefore compresses by about a hundred to one before any signal reaches the brain, and Chapter 4 described what the compression keeps: contrast rather than brightness, change rather than steady state, edges rather than surfaces. Estimates of the information rate of the optic nerve are on the order of ten megabits per second, less than a single compressed video stream.[3]

That capacity is not spread evenly. Fine resolution is confined to the fovea, a patch of densely packed cones covering about two degrees of the visual field, roughly the width of a thumbnail held at arm's length. Outside the fovea acuity collapses, and at fifteen degrees to one side there is a region with no receptors at all, where the optic nerve exits. This blind spot is about six degrees across, a dozen times the width of the full moon, and you have never seen it, because the brain fills it with whatever surrounds it.[4]

Nor does the eye hold still. It jumps about three times a second in rapid movements called saccades, resting for a few hundred milliseconds between jumps. During each jump the image sweeps across the retina at hundreds of degrees per second and vision is suppressed.[5] What arrives in the brain is not a stable, wide, high-resolution picture. It is a sequence of small, sharp, overlapping samples, each a fraction of a second long, separated by gaps, with a hole in each one. The stable scene you experience is not among the inputs. It is an output.

---

[1] Helmholtz, H. von (1867). *Handbuch der physiologischen Optik*. Leipzig: Voss. English edition: *Treatise on Physiological Optics*, vol. III, trans. J. P. C. Southall (Optical Society of America, 1925). The doctrine of unconscious inference is set out in §26 of vol. III.

[2] Curcio, C. A., Sloan, K. R., Kalina, R. E., & Hendrickson, A. E. (1990). Human photoreceptor topography. *Journal of Comparative Neurology*, 292(4), 497–523; Jonas, J. B., Schmidt, A. M., Müller-Bergh, J. A., Schlötzer-Schrehardt, U. M., & Naumann, G. O. H. (1992). Human optic nerve fiber count and optic disc size. *Investigative Ophthalmology & Visual Science*, 33(6), 2012–2018.

[3] Koch, K., McLean, J., Segev, R., Freed, M. A., Berry, M. J., Balasubramanian, V., & Sterling, P. (2006). How much the eye tells the brain. *Current Biology*, 16(14), 1428–1434.

[4] Ramachandran, V. S. (1992). Blind spots. *Scientific American*, 266(5), 86–91.

[5] Matin, E. (1974). Saccadic suppression: A review and an analysis. *Psychological Bulletin*, 81(12), 899–917; Rayner, K. (1998). Eye movements in reading and information processing: 20 years of research. *Psychological Bulletin*, 124(3), 372–422.

The same holds for the other senses. The cochlea delivers a running spectrum, not words. Touch delivers the deformation of skin, not the shape of the object. In every case the sense organ reports local physical quantities, and the rest is inference.

Bayes in One Paragraph

The mathematics of inference under uncertainty was worked out in the eighteenth century and is short enough to state in full. Suppose the brain must estimate some quantity, say the direction of a sound. Before the sound arrives there is a prior: a distribution over directions that encodes what is usually true, built from a lifetime of sounds. When the sound arrives there is a likelihood: for each possible direction, how probable are these particular sensations? Bayes's rule says that the posterior, the distribution the brain should act on, is proportional to the prior multiplied by the likelihood.[6] The prior says what to expect; the evidence says what was observed; the posterior is the compromise, and it leans toward whichever of the two is more precise.

Figure 6.2 shows the consequence for the simplest case, where both are bell curves. When the evidence is sharp, the posterior sits almost on the evidence, and the prior barely matters. When the evidence is noisy, the posterior sits near the prior, and the senses barely matter. Neither extreme is a failure. A system that always trusted its senses would be captured by every flicker of noise; a system that always trusted its prior would be blind. The optimal weighting is set by relative precision, and it changes from moment to moment as the quality of the evidence changes.





Figure 6.2. Combining a prior with sensory evidence. A: precise evidence pulls the posterior toward itself. B: the same prior with noisy evidence; the posterior stays near the prior. The weighting is set by the relative precisions.

This is the sense in which perception is inference. The brain does not compute Bayes's rule symbolically any more than a thrown ball solves differential equations. But the system behaves, to a good approximation, as the rule says it should, and the rest of this chapter is about the machinery that produces that behavior and the places where the approximation shows.

---

[6] Bayes, T. (1763). An essay towards solving a problem in the doctrine of chances. *Philosophical Transactions of the Royal Society of London*, 53, 370–418; Knill, D. C., & Pouget, A. (2004). The Bayesian brain: The role of uncertainty in neural coding and computation. *Trends in Neurosciences*, 27(12), 712–719.

Where do the priors come from? From Chapter 5. A prior is learned structure: the accumulated statistical regularities of a lifetime of input, written into synaptic weights by the plasticity mechanisms already described. The light-from-above prior is the clearest example. Light has come from above for the whole of evolutionary history and for the whole of each individual life, and the visual system assumes it. A disc shaded light on top is seen as a bump, a disc shaded light on the bottom as a dent, and turning the page swaps them (Figure 6.3). No one is taught this. It is in the weights.[7]



Discs lighter on top look like bumps; discs lighter on the bottom look like dents. Rotate the page and they swap.

Figure 6.3. The light-from-above prior. A: discs shaded lighter on top are seen as bumps and the others as dents. B: the same image rotated by 180 degrees; every disc reverses. The shading is identical in both panels; only the assumption about where the light is differs.

The Hierarchy

Perception is carried out by a hierarchy of cortical areas, and the visual hierarchy is the best understood (Figure 6.4). Retinal ganglion cells project to the lateral geniculate nucleus of the thalamus, the LGN, and the LGN projects to the primary visual cortex, V1, at the back of the brain. From V1 the signal passes to V2, V4, and the inferotemporal cortex, IT, along what is called the ventral stream, and in parallel to areas specialized for motion and location along the dorsal stream.[8]

[7] Ramachandran, V. S. (1988). Perception of shape from shading. *Nature*, 331, 163–166.

[8] Ungerleider, L. G., & Mishkin, M. (1982). Two cortical visual systems. In D. J. Ingle, M. A. Goodale, & R. J. W. Mansfield (Eds.), *Analysis of Visual Behavior* (pp. 549–586). MIT Press; Felleman, D. J., & Van Essen, D. C. (1991). Distributed hierarchical processing in the primate cerebral cortex. *Cerebral Cortex*, 1(1), 1–47.




Figure 6.4. The ventral visual pathway. Receptive fields grow and preferences become more abstract at each stage. Feedforward connections carry evidence upward; feedback connections, which outnumber them, carry predictions and context downward. There is no feedback to the retina.

Two things change at each stage. The receptive field, the region of the visual field that can influence a neuron, grows, from a fraction of a degree in V1 to most of the visual field in IT. And the preferred stimulus becomes more abstract. A V1 neuron responds to an oriented edge at one place (Figure 6.10).[9] A V4 neuron responds to a curved contour or a color in a larger region. An IT neuron responds to an object, a face, or a hand, more or less regardless of where it appears, how large it is, or how it is lit.[10] The hierarchy builds invariance: the same thing is recognized as the same thing across the enormous variation in images that it can produce.

This feedforward sweep is fast. An image flashed for a few tens of milliseconds produces a selective response in IT about a hundred milliseconds later, and a human can categorize a scene as containing an animal or not in about a hundred and fifty milliseconds.[11] Convolutional neural networks were modeled on this sweep, and the best of them predict the responses of IT neurons to novel images better than any model built by hand.[12] This is the part of perception that artificial systems have reproduced.

But the sweep is not the whole hierarchy, nor even most of it. Feedback connections, running from each area back down to the areas below, outnumber the feedforward ones. The LGN, the thalamic relay that the retina feeds, receives only about a tenth of its synapses from the retina; the rest come from the cortex and the brainstem.[13] Anatomically, the visual system is not a pipeline from eye to cortex. It is a

[9] Hubel, D. H., & Wiesel, T. N. (1962). Receptive fields, binocular interaction and functional architecture in the cat's visual cortex. *Journal of Physiology*, 160(1), 106–154.

[10] Gross, C. G., Rocha-Miranda, C. E., & Bender, D. B. (1972). Visual properties of neurons in inferotemporal cortex of the macaque. *Journal of Neurophysiology*, 35(1), 96–111.

[11] Thorpe, S., Fize, D., & Marlot, C. (1996). Speed of processing in the human visual system. *Nature*, 381, 520–522; Hung, C. P., Kreiman, G., Poggio, T., & DiCarlo, J. J. (2005). Fast readout of object identity from macaque inferior temporal cortex. *Science*, 310(5749), 863–866.

[12] Yamins, D. L. K., Hong, H., Cadieu, C. F., Solomon, E. A., Seibert, D., & DiCarlo, J. J. (2014). Performance-optimized hierarchical models predict neural responses in higher visual cortex. *Proceedings of the National Academy of Sciences*, 111(23), 8619–8624.

[13] Sherman, S. M., & Guillery, R. W. (2006). *Exploring the Thalamus and Its Role in Cortical Function* (2nd ed.). MIT Press; Felleman, D. J., & Van Essen, D. C. (1991). Distributed hierarchical processing in the primate cerebral cortex. *Cerebral Cortex*, 1(1), 1–47.

loop, and the downward half is larger than the upward half. Any account of perception has to say what the downward half is for.

Predictive Coding

The account that has organized the field for the last three decades is called predictive coding, and it is a direct implementation of Helmholtz's idea in the anatomy of Figure 6.4.[14]

Each level of the hierarchy holds a hypothesis about what the level below is receiving. It sends that hypothesis downward as a prediction. The level below compares the prediction with what it actually has and sends upward only the difference, the prediction error. The level above uses the error to revise its hypothesis, sends a revised prediction, and the cycle repeats until the error is small. What ascends the hierarchy is not the image but the part of the image that was not expected (Figure 6.5A).




Figure 6.5. Predictive coding. A: each level sends predictions down and receives errors up; the proposed mapping onto the canonical microcircuit places error units in the superficial layers and prediction units in the deep layers. B: a simulated error signal for a tone repeated six times, replaced once, and repeated again. Error falls with repetition and spikes at the change.

The scheme has three consequences that look surprising until the scheme is understood. The first is that an expected stimulus produces less cortical activity than an unexpected one. If the prediction is good, the error is small, and the error is what is transmitted. The second is that the absence of an expected stimulus produces activity: a prediction with nothing to cancel it is itself an error. The third is that what a neuron responds to depends on context, because the prediction arriving from above depends on everything the higher level knows.

All three are observed. A stimulus repeated several times evokes a smaller response each time, in single neurons and in whole-brain imaging; this is called repetition suppression, and it is the single most

[14] Mumford, D. (1992). On the computational architecture of the neocortex. II. The role of cortico-cortical loops. *Biological Cybernetics*, 66(3), 241–251; Rao, R. P. N., & Ballard, D. H. (1999). Predictive coding in the visual cortex: A functional interpretation of some extra-classical receptive-field effects. *Nature Neuroscience*, 2(1), 79–87; Friston, K. (2005). A theory of cortical responses. *Philosophical Transactions of the Royal Society B*, 360(1456), 815–836.

reproducible phenomenon in sensory cortex (Figure 6.5B).[15] A tone omitted from a regular sequence evokes a response at the moment it should have occurred.[16] The deviant tone in a sequence of standards evokes a distinctive electrical signature at the scalp, the mismatch negativity, about one to two hundred milliseconds after it arrives; it is present in sleeping adults and newborn infants and reflects a prediction being violated rather than anything about the tone itself.[17] And neurons in V1 respond to a line most strongly when it ends inside their receptive field, a long-known puzzle called end-stopping, which the first predictive coding model of the visual cortex, published in 1999, reproduced without being designed to: a line that continues is predictable from its surroundings, and a line that stops is not.[18]

The scheme also fits the microcircuit of Chapter 4 in a specific way. The superficial layers of cortex, which project forward, carry activity dominated by fast gamma rhythms; the deep layers, which project backward, carry activity dominated by the slower alpha and beta rhythms. Predictive coding proposes that the superficial layers hold the error units and the deep layers the prediction units, so that errors ascend on gamma and predictions descend on alpha and beta. Recordings from several areas at once support the direction of this traffic.[19] It is a model, and the mapping is not settled, but it is the kind of model that could be wrong in detail, which is the kind worth having.

Illusions Are Correct Answers

If perception is inference, illusions are what inference looks like when the prior is right about the world and wrong about the picture. They are the most direct evidence we have for which priors the visual system holds.

In Adelson's checker-shadow figure (Figure 6.6), the squares marked A and B are printed in exactly the same grey. They do not look it, and they will not look it after you have measured them. The visual system has inferred a cylinder, a light source, and a shadow, and it has discounted the shadow before reporting the surface color of B. That is the correct computation. In a real scene, a surface in shadow that reflects as much light as a surface in the open really is lighter, and a visual system that reported raw luminance would misjudge every surface that fell in shade. The figure defeats the system by presenting a shadow with nothing behind it.[20]

---

[15] Grill-Spector, K., Henson, R., & Martin, A. (2006). Repetition and the brain: Neural models of stimulus-specific effects. *Trends in Cognitive Sciences*, 10(1), 14–23.

[16] Wacongne, C., Labyt, E., van Wassenhove, V., Bekinschtein, T., Naccache, L., & Dehaene, S. (2011). Evidence for a hierarchy of predictions and prediction errors in human cortex. *Proceedings of the National Academy of Sciences*, 108(51), 20754–20759.

[17] Näätänen, R., Gaillard, A. W. K., & Mäntysalo, S. (1978). Early selective-attention effect on evoked potential reinterpreted. *Acta Psychologica*, 42(4), 313–329; Näätänen, R., Paavilainen, P., Rinne, T., & Alho, K. (2007). The mismatch negativity (MMN) in basic research of central auditory processing: A review. *Clinical Neurophysiology*, 118(12), 2544–2590.

[18] Hubel, D. H., & Wiesel, T. N. (1965). Receptive fields and functional architecture in two nonstriate visual areas (18 and 19) of the cat. *Journal of Neurophysiology*, 28(2), 229–289; Rao, R. P. N., & Ballard, D. H. (1999). Predictive coding in the visual cortex: A functional interpretation of some extra-classical receptive-field effects. *Nature Neuroscience*, 2(1), 79–87. End-stopped ("hypercomplex") cells were first described by Hubel and Wiesel.

[19] Bastos, A. M., Usrey, W. M., Adams, R. A., Mangun, G. R., Fries, P., & Friston, K. J. (2012). Canonical microcircuits for predictive coding. *Neuron*, 76(4), 695–711; van Kerkoerle, T., Self, M. W., Dagnino, B., Gariel-Mathis, M.-A., Poort, J., van der Togt, C., & Roelfsema, P. R. (2014). Alpha and gamma oscillations characterize feedback and feedforward processing in monkey visual cortex. *Proceedings of the National Academy of Sciences*, 111(40), 14332–14341; Bastos, A. M., Vezoli, J., Bosman, C. A., Schoffelen, J.-M., Oostenveld, R., Dowdall, J. R., De Weerd, P., Kennedy, H., & Fries, P. (2015). Visual areas exert feedforward and feedback influences through distinct frequency channels. *Neuron*, 85(2), 390–401.

[20] Adelson, E. H. (2000). Lightness perception and lightness illusions. In M. S. Gazzaniga (Ed.), *The New Cognitive Neurosciences* (2nd ed., pp. 339–351). MIT Press.




Figure 6.6. Adelson's checker-shadow illusion. The squares marked A and B are the same shade of grey. The visual system infers a shadow and discounts it, which is the right inference for a real scene. (Source: Edward H. Adelson, vectorized by Wikimedia Commons user Pbroks13, CC BY-SA 4.0.)

The Kanizsa triangle (Figure 6.7A) contains no triangle. Three discs with wedges removed and three corner fragments are arranged so that the most probable cause of the image is a white triangle lying on top of three black discs and an outlined triangle. The visual system reports that cause, complete with edges that are not in the image and a surface that looks whiter than the identical white around it. Neurons in V2 respond to these illusory contours as if they were real, which, under the hypothesis, they are.[21]

[21] Kanizsa, G. (1955). Margini quasi-percettivi in campi con stimolazione omogenea. *Rivista di Psicologia*, 49(1), 7–30; von der Heydt, R., Peterhans, E., & Baumgartner, G. (1984). Illusory contours and cortical neuron responses. *Science*, 224(4654), 1260–1262.




Figure 6.7. Two illusions as inferences. A: the Kanizsa triangle; the occluding white triangle is inferred, not drawn. B: the Müller-Lyer figure; the two horizontal lines are the same length but are read as corners at different depths.

In the Müller-Lyer figure (Figure 6.7B) two equal lines look unequal. One explanation, due to Richard Gregory, is that the fins are read as the edges of corners in a carpentered world: arrowheads as the near corner of a building, arrow tails as the far corner of a room. A far corner that subtends the same angle as a near one must be longer, and the system scales accordingly.[22] The explanation is debated, and that is the point. Each illusion is a probe, and arguments about illusions are arguments about which prior the system is using.

The hollow-mask illusion is the strongest of all. A face mask viewed from the inside, concave, is seen as convex, a normal face, even when it is slowly rotating and stereo vision and shading both report the truth. The prior that faces are convex is so strong that it overrides the evidence completely. The illusion weakens at close range, where stereo evidence becomes precise enough to win, and it is measurably weaker in people with schizophrenia, an observation to which the chapter returns.[23]

What all of these show is that the output of the perceptual system is not the image and not the world but the posterior, and that the posterior can be moved by manipulating either the evidence or the prior.

Attention as Precision

Bayes's rule weights evidence by its precision, and the brain cannot know the precision of a signal without estimating it. That estimate has to be represented somewhere and has to change what the circuit does. The proposal that follows from predictive coding is that this is what attention is: the gain applied to prediction errors, raised where the evidence is expected to be reliable and lowered where it is not.[24]

---

[22] Müller-Lyer, F. C. (1889). Optische Urteilstäuschungen. *Archiv für Anatomie und Physiologie, Physiologische Abteilung*, Supplement, 263–270; Gregory, R. L. (1963). Distortion of visual space as inappropriate constancy scaling. *Nature*, 199, 678–680.

[23] Gregory, R. L. (1970). *The Intelligent Eye*. Weidenfeld & Nicolson; Dima, D., Roiser, J. P., Dietrich, D. E., Bonnemann, C., Lanfermann, H., Emrich, H. M., & Dillo, W. (2009). Understanding why patients with schizophrenia do not perceive the hollow-mask illusion using dynamic causal modelling. *NeuroImage*, 46(4), 1180–1186.

[24] Feldman, H., & Friston, K. J. (2010). Attention, uncertainty, and free-energy. *Frontiers in Human Neuroscience*, 4, 215.

The proposal unifies a great deal. Attention to a location increases the response of neurons whose receptive fields cover it and decreases the response of neighbors, which is the biased competition of Chapter 4's lateral inhibition with a top-down bias setting the winner.[25] Attention increases the gamma synchrony of the attended population, which, through the oscillatory gating described in Chapter 4, lets its spikes arrive during the receptive phase of the next area and so increases their weight.[26] And attention makes the attended evidence count for more in the posterior, which is what raising its precision means.

Precision also has a chemistry, and it is the chemistry of Chapter 3. Acetylcholine, released from the basal forebrain into cortex, increases the gain of feedforward sensory input relative to recurrent and feedback input; a cholinergic cortex trusts its senses more and its expectations less.[27] One influential account assigns acetylcholine to expected uncertainty, the known unreliability of a familiar cue, and norepinephrine to unexpected uncertainty, the moment when the world changes and the current model should be discarded.[28] The noradrenergic burst that accompanies a surprise is, on this reading, a global instruction to lower the precision of every prediction at once.

The cost of precision weighting is that what is not attended is barely seen. In the best-known demonstration, observers counting passes in a basketball video fail to notice a person in a gorilla suit walking through the middle of the scene.[29] In change blindness, large alterations to a scene go unnoticed if they coincide with a blink or a cut.[30] These are not failures of the eye; the gorilla was on the retina for several seconds. They are the consequence of a system that transmits only what it has been told to find surprising.

Combining the Senses

The clearest quantitative test of the Bayesian account uses two senses at once. If the brain weights evidence by precision, then when vision and touch both report the width of an object, the combined estimate should lie between them, closer to the more reliable sense, and should be more precise than either alone. The weights can be computed exactly from the reliability of each sense measured separately.

In 2002 Marc Ernst and Martin Banks did this experiment with a bar that observers could see and feel at the same time, degrading vision by adding noise to the display. With clear vision, the estimate followed the eyes. As the visual noise increased, the weight shifted toward touch, and at every noise level

---

[25] Desimone, R., & Duncan, J. (1995). Neural mechanisms of selective visual attention. *Annual Review of Neuroscience*, 18, 193–222.

[26] Fries, P., Reynolds, J. H., Rorie, A. E., & Desimone, R. (2001). Modulation of oscillatory neuronal synchronization by selective visual attention. *Science*, 291(5508), 1560–1563; Fries, P. (2015). Rhythms for cognition: Communication through coherence. *Neuron*, 88(1), 220–235.

[27] Hasselmo, M. E. (2006). The role of acetylcholine in learning and memory. *Current Opinion in Neurobiology*, 16(6), 710–715.

[28] Yu, A. J., & Dayan, P. (2005). Uncertainty, neuromodulation, and attention. *Neuron*, 46(4), 681–692.

[29] Simons, D. J., & Chabris, C. F. (1999). Gorillas in our midst: Sustained inattentional blindness for dynamic events. *Perception*, 28(9), 1059–1074.

[30] Rensink, R. A., O'Regan, J. K., & Clark, J. J. (1997). To see or not to see: The need for attention to perceive changes in scenes. *Psychological Science*, 8(5), 368–373.

the observed weights matched the computed optimum (Figure 6.8).[31] The brain was not favoring vision as a rule. It was favoring whichever sense was more precise, trial by trial.




Figure 6.8. Precision-weighted combination of vision and touch. A: with a clear view, the combined estimate follows vision. B: with vision blurred, touch dominates. In both cases the combined estimate is narrower than either input, and the weights are set by the relative precisions.

Everyday perception is full of the same computation. The ventriloquist's voice appears to come from the dummy's mouth because vision locates things more precisely than hearing, so the posterior for the sound's location follows the visible moving mouth.[32] In the McGurk effect, a recording of one syllable dubbed onto a face mouthing a different syllable is heard as a third syllable, a compromise between what was heard and what was seen.[33] The senses are not separate channels to a central viewer. They are sources of evidence, pooled in proportion to how much each can be trusted.

Perception Is Active

Chapter 1 said that the brain generates and the world corrects, and the account so far has treated the brain as if it sat still and waited for evidence. It does not. It moves the sense organs to get the evidence it wants, and that changes the problem in two ways.

The first is that the brain must distinguish sensation caused by the world from sensation caused by its own movement. When the eye jumps ten degrees, the image sweeps ten degrees across the retina, exactly as it would if the world had jumped. It does not look that way. The solution, proposed independently by von Holst and by Sperry in 1950, is that every motor command is copied and sent to the sensory system, which uses it to predict the sensory consequence of the movement and subtract it.[34] The copy is called the efference copy, the prediction is a forward model, and the comparison is shown in Figure 6.9. If the predicted slip matches the actual slip, the world is reported as stationary. Press gently

[31] Ernst, M. O., & Banks, M. S. (2002). Humans integrate visual and haptic information in a statistically optimal fashion. *Nature*, 415, 429–433.

[32] Alais, D., & Burr, D. (2004). The ventriloquist effect results from near-optimal bimodal integration. *Current Biology*, 14(3), 257–262.

[33] McGurk, H., & MacDonald, J. (1976). Hearing lips and seeing voices. *Nature*, 264, 746–748.

[34] von Holst, E., & Mittelstaedt, H. (1950). Das Reafferenzprinzip: Wechselwirkungen zwischen Zentralnervensystem und Peripherie. *Naturwissenschaften*, 37(20), 464–476; Sperry, R. W. (1950). Neural basis of the spontaneous optokinetic response produced by visual inversion. *Journal of Comparative and Physiological Psychology*, 43(6), 482–489.

on your eyelid and move the eye by hand: there is no command, no prediction, nothing is subtracted, and the world lurches. The cerebellum of Chapter 4, which learns to predict the sensory consequences of commands, is a principal site of this forward model.[35] The same mechanism is why you cannot tickle yourself: the sensation is predicted and cancelled before it is felt.[36]




Figure 6.9. Efference copy. A copy of each motor command is sent to a forward model that predicts the resulting sensory change. The prediction is subtracted from the actual sensation, so that self-caused changes are cancelled and only changes caused by the world remain.

The second is that movement is itself a tool of inference. A saccade is a decision about where evidence is most needed, and the sequence of fixations on a scene depends on the question being asked.[37] A rat sweeps its whiskers across an object at a rate it controls; a dog sniffs in bursts timed to its uncertainty; a reader's eyes land on the words that the sentence so far has made least predictable.[38] In each case the organism is not receiving evidence but sampling it, choosing the sample that will reduce its uncertainty most. Perception and action, kept apart in the textbooks, are two halves of one loop: the hypothesis determines where to look, and what is seen revises the hypothesis. Some theorists go further and treat action as inference too, the body moving so as to make the brain's predictions come true.[39] Whether or not one accepts that framing, the practical lesson is secure. An observer that cannot act is solving a harder problem than any brain has ever had to solve.

Learning the Priors

If perception rests on priors, the question of where they come from is the question of how perception is learned, and the answer connects this chapter to the last.

---

[35] Wolpert, D. M., Miall, R. C., & Kawato, M. (1998). Internal models in the cerebellum. *Trends in Cognitive Sciences*, 2(9), 338–347.

[36] Blakemore, S.-J., Wolpert, D. M., & Frith, C. D. (1998). Central cancellation of self-produced tickle sensation. *Nature Neuroscience*, 1(7), 635–640.

[37] Yarbus, A. L. (1967). *Eye Movements and Vision*. Plenum Press.

[38] Kleinfeld, D., Ahissar, E., & Diamond, M. E. (2006). Active sensation: Insights from the rodent vibrissa sensorimotor system. *Current Opinion in Neurobiology*, 16(4), 435–444; Rayner, K. (1998). Eye movements in reading and information processing: 20 years of research. *Psychological Bulletin*, 124(3), 372–422.

[39] Friston, K. (2010). The free-energy principle: A unified brain theory? *Nature Reviews Neuroscience*, 11(2), 127–138.

Some priors are built in. Newborns orient to face-like patterns within hours, and the light-from-above assumption is present in several species that have never been taught it.[40] But most of the structure of sensory cortex is learned from the statistics of the input, and the learning has the properties Chapter 5 would predict. It is slow, it is gated, and it has a window.

The window was discovered by Hubel and Wiesel in the 1960s. A kitten with one eye closed for a few weeks early in life loses, permanently, the cortical representation of that eye; the same closure in an adult does nothing.[41] The period during which experience can reorganize the visual cortex is called the critical period, and it closes, in the cat, after a few months and in humans after a few years. Kittens raised in environments containing only vertical stripes grew up with cortices in which almost no neuron responded to horizontal edges, and they bumped into horizontal bars.[42] The critical period opens and closes under the control of inhibitory maturation and of the neuromodulators of Chapter 3; it is a time when the plasticity rules of Chapter 5 are turned up, and its closing is what makes adult perception stable and adult perceptual learning slow.[43]

What is learned during the window is the statistics of natural images, and that can be shown directly. In 1996 Olshausen and Field trained a simple model to represent patches of photographs using as few active units as possible. The units it learned were localized, oriented, band-pass filters, Figure 6.10, essentially the receptive fields that Hubel and Wiesel had found in V1 thirty years earlier.[44] Nothing about edges was built in. Edges are what the world contains, and a system that learns to predict the world ends up with detectors for them. The same procedure applied to natural sounds produces filters resembling those of the auditory nerve.[45] The receptive fields of sensory cortex are, to a first approximation, the priors of the natural world made into tissue.

---

[40] Johnson, M. H., Dziurawiec, S., Ellis, H., & Morton, J. (1991). Newborns' preferential tracking of face-like stimuli and its subsequent decline. *Cognition*, 40(1–2), 1–19; Hershberger, W. (1970). Attached-shadow orientation perceived as depth by chickens reared in an environment illuminated from below. *Journal of Comparative and Physiological Psychology*, 73(3), 407–411.


[41] Wiesel, T. N., & Hubel, D. H. (1963). Single-cell responses in striate cortex of kittens deprived of vision in one eye. *Journal of Neurophysiology*, 26(6), 1003–1017; Hubel, D. H., & Wiesel, T. N. (1970). The period of susceptibility to the physiological effects of unilateral eye closure in kittens. *Journal of Physiology*, 206(2), 419–436.

[42] Blakemore, C., & Cooper, G. F. (1970). Development of the brain depends on the visual environment. *Nature*, 228, 477–478.

[43] Hensch, T. K. (2005). Critical period plasticity in local cortical circuits. *Nature Reviews Neuroscience*, 6(11), 877–888.

[44] Olshausen, B. A., & Field, D. J. (1996). Emergence of simple-cell receptive field properties by learning a sparse code for natural images. *Nature*, 381, 607–609.

[45] Lewicki, M. S. (2002). Efficient coding of natural sounds. *Nature Neuroscience*, 5(4), 356–363.



Receptive fields of V1 simple cells (schematic): localized, oriented, band-pass. Light = excitatory region, dark = inhibitory.

Figure 6.10. Receptive fields of the kind found in primary visual cortex: each cell responds to an edge of one orientation and scale at one location. Fields of this form emerge in models trained only to represent natural images efficiently.

This learning never fully stops. Wear prism goggles that shift the world sideways and reaching errors vanish in minutes, as the cerebellar forward model relearns.[46] Wear goggles that invert the world and within days it begins to look upright again.[47] Spend a month in a room lit by a single color and color constancy recalibrates.[48] The adult perceptual system is a model under continual revision, slow in its deep layers and fast at its edges, exactly as the two consolidation clocks of Chapter 5 would suggest.

When Inference Goes Wrong

A system that constructs its percepts from priors and evidence can fail in two directions, and both are seen in the clinic.

When the evidence is removed, the priors run unopposed. People who lose their vision late in life through disease of the eye frequently begin to see vivid, detailed hallucinations, faces, patterns, figures in period dress, while knowing perfectly well that nothing is there; the condition is named for Charles Bonnet, who described it in his grandfather in 1760.[49] A visual cortex that has lost its input does not go silent. It continues to generate hypotheses, and with no error signal to correct them they are experienced as sight. Phantom limbs are the same phenomenon in another modality: the body model persists after the body part is gone, and its predictions, unanswered, are felt.[50]

When the precision of evidence and prior is misweighted, perception bends. The hollow-mask illusion is weaker in schizophrenia, which suggests that priors there have lost some of their grip; at the same time,

---

[46] Martin, T. A., Keating, J. G., Goodkin, H. P., Bastian, A. J., & Thach, W. T. (1996). Throwing while looking through prisms. I. Focal olivocerebellar lesions impair adaptation. *Brain*, 119(4), 1183–1198.

[47] Stratton, G. M. (1897). Vision without inversion of the retinal image. *Psychological Review*, 4(4), 341–360 and 4(5), 463–481; Kohler, I. (1962). Experiments with goggles. *Scientific American*, 206(5), 62–72.

[48] Neitz, J., Carroll, J., Yamauchi, Y., Neitz, M., & Williams, D. R. (2002). Color perception is mediated by a plastic neural mechanism that is adjustable in adults. *Neuron*, 35(4), 783–792.

[49] Bonnet, C. (1760). *Essai analytique sur les facultés de l'âme*. Copenhagen: Philibert; ffytche, D. H., Howard, R. J., Brammer, M. J., David, A., Woodruff, P., & Williams, S. (1998). The anatomy of conscious vision: An fMRI study of visual hallucinations. *Nature Neuroscience*, 1(8), 738–742.

[50] Ramachandran, V. S., & Hirstein, W. (1998). The perception of phantom limbs: The D. O. Hebb lecture. *Brain*, 121(9), 1603–1630.

hallucinations and delusions can be understood as priors with too much precision, or as noise in the error channel that is read as signal. The two readings are not contradictory; a system can weight its priors too strongly at one level and too weakly at another.[51] One account of autistic perception proposes the opposite imbalance, sensory precision too high relative to the priors, so that the world is experienced in unfiltered detail and small deviations from expectation are overwhelming.[52] All of these are hypotheses, not settled findings, and they are offered here because they show what the framework buys: a vocabulary in which disorders of perception are disorders of weighting, and the weights are set by mechanisms, inhibition, acetylcholine, dopamine, and oscillatory gain, that are known and can be measured.

Implications for Artificial Intelligence

Perception is the domain in which artificial systems most clearly match the brain and in which the comparison is most instructive about what they lack.

First, the feedforward sweep has been reproduced. Deep convolutional networks trained to classify images develop a hierarchy of features, from oriented edges to object parts, that resembles the ventral stream closely enough to predict the responses of its neurons. The resemblance is not a coincidence; both are solutions to the same statistical problem, and the fact that gradient descent and evolution arrived at the same place is evidence that the place is not arbitrary.[53]

Second, the loops have not been. Standard networks have no feedback, no prediction, and no error signal at inference time; they map an input to an output in one pass. The brain spends most of its visual anatomy on the other direction. Adversarial examples, in which an imperceptible change to an image produces a confident misclassification, are what a system looks like when it has evidence but no priors with which to check it.[54] A brain confronted with such an image would predict a cat, compare, find the error large, and look again.

Third, precision is missing. The attention mechanism of transformers weights inputs by learned relevance, which is a cousin of precision weighting, but there is nothing in most artificial systems that estimates how reliable each input is and discounts it accordingly, nor a global signal, like norepinephrine, that says the model should be distrusted now.[55] Systems that must operate on degraded sensors, in fog or in noise, need exactly this.

---

[51] Fletcher, P. C., & Frith, C. D. (2009). Perceiving is believing: A Bayesian approach to explaining the positive symptoms of schizophrenia. *Nature Reviews Neuroscience*, 10(1), 48–58; Sterzer, P., Adams, R. A., Fletcher, P., Frith, C., Lawrie, S. M., Muckli, L., Petrovic, P., Uhlhaas, P., Voss, M., & Corlett, P. R. (2018). The predictive coding account of psychosis. *Biological Psychiatry*, 84(9), 634–643.

[52] Pellicano, E., & Burr, D. (2012). When the world becomes 'too real': A Bayesian explanation of autistic perception. *Trends in Cognitive Sciences*, 16(10), 504–510; Lawson, R. P., Rees, G., & Friston, K. J. (2014). An aberrant precision account of autism. *Frontiers in Human Neuroscience*, 8, 302.

[53] Yamins, D. L. K., & DiCarlo, J. J. (2016). Using goal-driven deep learning models to understand sensory cortex. *Nature Neuroscience*, 19(3), 356–365.

[54] Szegedy, C., Zaremba, W., Sutskever, I., Bruna, J., Erhan, D., Goodfellow, I., & Fergus, R. (2014). Intriguing properties of neural networks. *International Conference on Learning Representations (ICLR)*; Goodfellow, I. J., Shlens, J., & Szegedy, C. (2015). Explaining and harnessing adversarial examples. *International Conference on Learning Representations (ICLR)*.

[55] Vaswani, A., Shazeer, N., Parmar, N., Uszkoreit, J., Jones, L., Gomez, A. N., Kaiser, Ł., & Polosukhin, I. (2017). Attention is all you need. *Advances in Neural Information Processing Systems*, 30.

Fourth, generative models are the right direction. A network that can generate the data it classifies has, in effect, a prior and a likelihood and can compute something like a posterior; variational autoencoders and diffusion models are explicit attempts to build such machinery, and the best current explanations of cortex are, in essence, hierarchical generative models trained by prediction error.[56] Whether predictive coding can replace backpropagation as a learning rule is an open research question with a biological existence proof on one side.[57]

Fifth, perception should be active. A system that chooses where to sample is solving an easier problem than one that must process everything, and robotics has begun to borrow the saccade, the forward model, and the efference copy for exactly the reasons the brain uses them.[58] An agent that cannot predict the sensory consequences of its own actions cannot tell what it did from what the world did, and that is a fatal confusion for anything that must learn from experience.

The Central Lesson

The senses deliver evidence that does not determine the world, and the brain supplies the rest. It holds a model of what is usually true, written into its synapses by the plasticity of Chapter 5, and it combines that model with the incoming evidence in proportion to how much each can be trusted. The combination is carried out by a hierarchy in which predictions descend and errors ascend, so that what the cortex transmits is not the image but its surprise. Attention sets the trust, the neuromodulators of Chapter 3 set the attention, and action chooses what evidence to gather next. Illusions, hallucinations, and the stability of the visual world are all the same mechanism seen from different sides. You do not see what is there. You see your best current hypothesis about what is there, and most of the time it is right.

Next Chapter

Chapter 7: Emotion and the Body — How Internal States Tell the Brain What Matters

References and Attribution

Figure Attribution

Figures 6.1, 6.2, 6.3, 6.4, 6.5, 6.7, 6.8, 6.9, and 6.10 were drawn for this book. The curves in Figures 6.3 and 6.8, the error trace in Figure 6.5B, and the receptive fields in Figure 6.10 are illustrative computations, not recorded data.

---

[56] Dayan, P., Hinton, G. E., Neal, R. M., & Zemel, R. S. (1995). The Helmholtz machine. *Neural Computation*, 7(5), 889–904; Kingma, D. P., & Welling, M. (2014). Auto-encoding variational Bayes. *International Conference on Learning Representations (ICLR)*; Ho, J., Jain, A., & Abbeel, P. (2020). Denoising diffusion probabilistic models. *Advances in Neural Information Processing Systems*, 33.

[57] Whittington, J. C. R., & Bogacz, R. (2017). An approximation of the error backpropagation algorithm in a predictive coding network with local Hebbian synaptic plasticity. *Neural Computation*, 29(5), 1229–1262; Millidge, B., Seth, A., & Buckley, C. L. (2022). Predictive coding: A theoretical and experimental review. *arXiv*, 2107.12979.

[58] Bajcsy, R., Aloimonos, Y., & Tsotsos, J. K. (2018). Revisiting active perception. *Autonomous Robots*, 42(2), 177–196.

Figure 6.6: “Checker shadow illusion” by Edward H. Adelson, vectorized by Wikimedia Commons user Pbroks13, CC BY-SA 4.0, via Wikimedia Commons.

Epigraph

Hermann von Helmholtz, *Treatise on Physiological Optics*, vol. III, §26, trans. J. P. C. Southall (Optical Society of America, 1925); first published in German in 1867.

References

Adelson, E. H. (2000). Lightness perception and lightness illusions. In M. S. Gazzaniga (Ed.), *The New Cognitive Neurosciences* (2nd ed., pp. 339–351). MIT Press.

Alais, D., & Burr, D. (2004). The ventriloquist effect results from near-optimal bimodal integration. *Current Biology*, 14(3), 257–262.

Bajcsy, R., Aloimonos, Y., & Tsotsos, J. K. (2018). Revisiting active perception. *Autonomous Robots*, 42(2), 177–196.

Bastos, A. M., Usrey, W. M., Adams, R. A., Mangun, G. R., Fries, P., & Friston, K. J. (2012). Canonical microcircuits for predictive coding. *Neuron*, 76(4), 695–711.

Bastos, A. M., Vezoli, J., Bosman, C. A., Schoffelen, J.-M., Oostenveld, R., Dowdall, J. R., De Weerd, P., Kennedy, H., & Fries, P. (2015). Visual areas exert feedforward and feedback influences through distinct frequency channels. *Neuron*, 85(2), 390–401.

Bayes, T. (1763). An essay towards solving a problem in the doctrine of chances. *Philosophical Transactions of the Royal Society of London*, 53, 370–418.

Blakemore, C., & Cooper, G. F. (1970). Development of the brain depends on the visual environment. *Nature*, 228, 477–478.

Blakemore, S.-J., Wolpert, D. M., & Frith, C. D. (1998). Central cancellation of self-produced tickle sensation. *Nature Neuroscience*, 1(7), 635–640.

Bonnet, C. (1760). *Essai analytique sur les facultés de l’âme*. Copenhagen: Philibert.

Curcio, C. A., Sloan, K. R., Kalina, R. E., & Hendrickson, A. E. (1990). Human photoreceptor topography. *Journal of Comparative Neurology*, 292(4), 497–523.

Dayan, P., Hinton, G. E., Neal, R. M., & Zemel, R. S. (1995). The Helmholtz machine. *Neural Computation*, 7(5), 889–904.

Desimone, R., & Duncan, J. (1995). Neural mechanisms of selective visual attention. *Annual Review of Neuroscience*, 18, 193–222.

Dima, D., Roiser, J. P., Dietrich, D. E., Bonnemann, C., Lanfermann, H., Emrich, H. M., & Dillo, W. (2009). Understanding why patients with schizophrenia do not perceive the hollow-mask illusion using dynamic causal modelling. *NeuroImage*, 46(4), 1180–1186.

Ernst, M. O., & Banks, M. S. (2002). Humans integrate visual and haptic information in a statistically optimal fashion. *Nature*, 415, 429–433.

Feldman, H., & Friston, K. J. (2010). Attention, uncertainty, and free-energy. *Frontiers in Human Neuroscience*, 4, 215.

Felleman, D. J., & Van Essen, D. C. (1991). Distributed hierarchical processing in the primate cerebral cortex. *Cerebral Cortex*, 1(1), 1–47.

ffytche, D. H., Howard, R. J., Brammer, M. J., David, A., Woodruff, P., & Williams, S. (1998). The anatomy of conscious vision: An fMRI study of visual hallucinations. *Nature Neuroscience*, 1(8), 738–742.

Fletcher, P. C., & Frith, C. D. (2009). Perceiving is believing: A Bayesian approach to explaining the positive symptoms of schizophrenia. *Nature Reviews Neuroscience*, 10(1), 48–58.

Fries, P. (2015). Rhythms for cognition: Communication through coherence. *Neuron*, 88(1), 220–235.

Fries, P., Reynolds, J. H., Rorie, A. E., & Desimone, R. (2001). Modulation of oscillatory neuronal synchronization by selective visual attention. *Science*, 291(5508), 1560–1563.

Friston, K. (2005). A theory of cortical responses. *Philosophical Transactions of the Royal Society B*, 360(1456), 815–836.

Friston, K. (2010). The free-energy principle: A unified brain theory? *Nature Reviews Neuroscience*, 11(2), 127–138.

Goodfellow, I. J., Shlens, J., & Szegedy, C. (2015). Explaining and harnessing adversarial examples. *International Conference on Learning Representations (ICLR)*.

Gregory, R. L. (1963). Distortion of visual space as inappropriate constancy scaling. *Nature*, 199, 678–680.

Gregory, R. L. (1970). *The Intelligent Eye*. Weidenfeld & Nicolson.

Grill-Spector, K., Henson, R., & Martin, A. (2006). Repetition and the brain: Neural models of stimulus-specific effects. *Trends in Cognitive Sciences*, 10(1), 14–23.

Gross, C. G., Rocha-Miranda, C. E., & Bender, D. B. (1972). Visual properties of neurons in inferotemporal cortex of the macaque. *Journal of Neurophysiology*, 35(1), 96–111.

Hasselmo, M. E. (2006). The role of acetylcholine in learning and memory. *Current Opinion in Neurobiology*, 16(6), 710–715.

Helmholtz, H. von (1867). *Handbuch der physiologischen Optik*. Leipzig: Voss. English edition: *Treatise on Physiological Optics*, vol. III, trans. J. P. C. Southall (Optical Society of America, 1925).

Hensch, T. K. (2005). Critical period plasticity in local cortical circuits. *Nature Reviews Neuroscience*, 6(11), 877–888.

Hershberger, W. (1970). Attached-shadow orientation perceived as depth by chickens reared in an environment illuminated from below. *Journal of Comparative and Physiological Psychology*, 73(3), 407–411.

Ho, J., Jain, A., & Abbeel, P. (2020). Denoising diffusion probabilistic models. *Advances in Neural Information Processing Systems*, 33.

Hubel, D. H., & Wiesel, T. N. (1962). Receptive fields, binocular interaction and functional architecture in the cat's visual cortex. *Journal of Physiology*, 160(1), 106–154.

Hubel, D. H., & Wiesel, T. N. (1965). Receptive fields and functional architecture in two nonstriate visual areas (18 and 19) of the cat. *Journal of Neurophysiology*, 28(2), 229–289.

Hubel, D. H., & Wiesel, T. N. (1970). The period of susceptibility to the physiological effects of unilateral eye closure in kittens. *Journal of Physiology*, 206(2), 419–436.

Hung, C. P., Kreiman, G., Poggio, T., & DiCarlo, J. J. (2005). Fast readout of object identity from macaque inferior temporal cortex. *Science*, 310(5749), 863–866.

Johnson, M. H., Dziurawiec, S., Ellis, H., & Morton, J. (1991). Newborns' preferential tracking of face-like stimuli and its subsequent decline. *Cognition*, 40(1–2), 1–19.

Jonas, J. B., Schmidt, A. M., Müller-Bergh, J. A., Schlötzer-Schrehardt, U. M., & Naumann, G. O. H. (1992). Human optic nerve fiber count and optic disc size. *Investigative Ophthalmology & Visual Science*, 33(6), 2012–2018.

Kanizsa, G. (1955). Margini quasi-percettivi in campi con stimolazione omogenea. *Rivista di Psicologia*, 49(1), 7–30.

Kingma, D. P., & Welling, M. (2014). Auto-encoding variational Bayes. *International Conference on Learning Representations (ICLR)*.

Kleinfeld, D., Ahissar, E., & Diamond, M. E. (2006). Active sensation: Insights from the rodent vibrissa sensorimotor system. *Current Opinion in Neurobiology*, 16(4), 435–444.

Knill, D. C., & Pouget, A. (2004). The Bayesian brain: The role of uncertainty in neural coding and computation. *Trends in Neurosciences*, 27(12), 712–719.

Koch, K., McLean, J., Segev, R., Freed, M. A., Berry, M. J., Balasubramanian, V., & Sterling, P. (2006). How much the eye tells the brain. *Current Biology*, 16(14), 1428–1434.

Kohler, I. (1962). Experiments with goggles. *Scientific American*, 206(5), 62–72.

Lawson, R. P., Rees, G., & Friston, K. J. (2014). An aberrant precision account of autism. *Frontiers in Human Neuroscience*, 8, 302.

Lewicki, M. S. (2002). Efficient coding of natural sounds. *Nature Neuroscience*, 5(4), 356–363.

Martin, T. A., Keating, J. G., Goodkin, H. P., Bastian, A. J., & Thach, W. T. (1996). Throwing while looking through prisms. I. Focal olivocerebellar lesions impair adaptation. *Brain*, 119(4), 1183–1198.

Matin, E. (1974). Saccadic suppression: A review and an analysis. *Psychological Bulletin*, 81(12), 899–917.

McGurk, H., & MacDonald, J. (1976). Hearing lips and seeing voices. *Nature*, 264, 746–748.

Millidge, B., Seth, A., & Buckley, C. L. (2022). Predictive coding: A theoretical and experimental review. *arXiv*, 2107.12979.

Mumford, D. (1992). On the computational architecture of the neocortex. II. The role of cortico-cortical loops. *Biological Cybernetics*, 66(3), 241–251.

Müller-Lyer, F. C. (1889). Optische Urteilstäuschungen. *Archiv für Anatomie und Physiologie, Physiologische Abteilung*, Supplement, 263–270.

Neitz, J., Carroll, J., Yamauchi, Y., Neitz, M., & Williams, D. R. (2002). Color perception is mediated by a plastic neural mechanism that is adjustable in adults. *Neuron*, 35(4), 783–792.

Näätänen, R., Gaillard, A. W. K., & Mäntysalo, S. (1978). Early selective-attention effect on evoked potential reinterpreted. *Acta Psychologica*, 42(4), 313–329.

Näätänen, R., Paavilainen, P., Rinne, T., & Alho, K. (2007). The mismatch negativity (MMN) in basic research of central auditory processing: A review. *Clinical Neurophysiology*, 118(12), 2544–2590.

Olshausen, B. A., & Field, D. J. (1996). Emergence of simple-cell receptive field properties by learning a sparse code for natural images. *Nature*, 381, 607–609.

Pellicano, E., & Burr, D. (2012). When the world becomes ‘too real’: A Bayesian explanation of autistic perception. *Trends in Cognitive Sciences*, 16(10), 504–510.

Ramachandran, V. S. (1988). Perception of shape from shading. *Nature*, 331, 163–166.

Ramachandran, V. S. (1992). Blind spots. *Scientific American*, 266(5), 86–91.

Ramachandran, V. S., & Hirstein, W. (1998). The perception of phantom limbs: The D. O. Hebb lecture. *Brain*, 121(9), 1603–1630.

Rao, R. P. N., & Ballard, D. H. (1999). Predictive coding in the visual cortex: A functional interpretation of some extra-classical receptive-field effects. *Nature Neuroscience*, 2(1), 79–87.

Rayner, K. (1998). Eye movements in reading and information processing: 20 years of research. *Psychological Bulletin*, 124(3), 372–422.

Rensink, R. A., O’Regan, J. K., & Clark, J. J. (1997). To see or not to see: The need for attention to perceive changes in scenes. *Psychological Science*, 8(5), 368–373.

Sherman, S. M., & Guillery, R. W. (2006). *Exploring the Thalamus and Its Role in Cortical Function* (2nd ed.). MIT Press.

Simons, D. J., & Chabris, C. F. (1999). Gorillas in our midst: Sustained inattentional blindness for dynamic events. *Perception*, 28(9), 1059–1074.

Sperry, R. W. (1950). Neural basis of the spontaneous optokinetic response produced by visual inversion. *Journal of Comparative and Physiological Psychology*, 43(6), 482–489.

Sterzer, P., Adams, R. A., Fletcher, P., Frith, C., Lawrie, S. M., Muckli, L., Petrovic, P., Uhlhaas, P., Voss, M., & Corlett, P. R. (2018). The predictive coding account of psychosis. *Biological Psychiatry*, 84(9), 634–643.

Stratton, G. M. (1897). Vision without inversion of the retinal image. *Psychological Review*, 4(4), 341–360 and 4(5), 463–481.

Szegedy, C., Zaremba, W., Sutskever, I., Bruna, J., Erhan, D., Goodfellow, I., & Fergus, R. (2014). Intriguing properties of neural networks. *International Conference on Learning Representations (ICLR)*.

Thorpe, S., Fize, D., & Marlot, C. (1996). Speed of processing in the human visual system. *Nature*, 381, 520–522.

Ungerleider, L. G., & Mishkin, M. (1982). Two cortical visual systems. In D. J. Ingle, M. A. Goodale, & R. J. W. Mansfield (Eds.), *Analysis of Visual Behavior* (pp. 549–586). MIT Press.

van Kerkoerle, T., Self, M. W., Dagnino, B., Gariel-Mathis, M.-A., Poort, J., van der Togt, C., & Roelfsema, P. R. (2014). Alpha and gamma oscillations characterize feedback and feedforward processing in monkey visual cortex. *Proceedings of the National Academy of Sciences*, 111(40), 14332–14341.

Vaswani, A., Shazeer, N., Parmar, N., Uszkoreit, J., Jones, L., Gomez, A. N., Kaiser, Ł., & Polosukhin, I. (2017). Attention is all you need. *Advances in Neural Information Processing Systems*, 30.

von der Heydt, R., Peterhans, E., & Baumgartner, G. (1984). Illusory contours and cortical neuron responses. *Science*, 224(4654), 1260–1262.

von Holst, E., & Mittelstaedt, H. (1950). Das Reafferenzprinzip: Wechselwirkungen zwischen Zentralnervensystem und Peripherie. *Naturwissenschaften*, 37(20), 464–476.

Wacongne, C., Labyt, E., van Wassenhove, V., Bekinschtein, T., Naccache, L., & Dehaene, S. (2011). Evidence for a hierarchy of predictions and prediction errors in human cortex. *Proceedings of the National Academy of Sciences*, 108(51), 20754–20759.

Whittington, J. C. R., & Bogacz, R. (2017). An approximation of the error backpropagation algorithm in a predictive coding network with local Hebbian synaptic plasticity. *Neural Computation*, 29(5), 1229–1262.

Wiesel, T. N., & Hubel, D. H. (1963). Single-cell responses in striate cortex of kittens deprived of vision in one eye. *Journal of Neurophysiology*, 26(6), 1003–1017.

Wolpert, D. M., Miall, R. C., & Kawato, M. (1998). Internal models in the cerebellum. *Trends in Cognitive Sciences*, 2(9), 338–347.

Yamins, D. L. K., & DiCarlo, J. J. (2016). Using goal-driven deep learning models to understand sensory cortex. *Nature Neuroscience*, 19(3), 356–365.

Yamins, D. L. K., Hong, H., Cadieu, C. F., Solomon, E. A., Seibert, D., & DiCarlo, J. J. (2014). Performance-optimized hierarchical models predict neural responses in higher visual cortex. *Proceedings of the National Academy of Sciences*, 111(23), 8619–8624.

Yarbus, A. L. (1967). *Eye Movements and Vision*. Plenum Press.

Yu, A. J., & Dayan, P. (2005). Uncertainty, neuromodulation, and attention. *Neuron*, 46(4), 681–692.